

This document was prepared by Roy F. Weston, Inc., expressly for EPA. It shall not be released or disclosed, in whole or in part, without the express written permission of EPA.

Remedial Investigation Report
 ABC One-Hour Cleaners, Inc.
 Jacksonville, Onslow County, North Carolina
 Section: 3
 Revision: 1
 Date: November 1992
 Page: 38 of 61

TABLE 3-7
 SUMMARY OF MONITOR WELL CONSTRUCTION
 AT ABC ONE-HOUR CLEANERS, INC.

WELL NO.	TOTAL BOREHOLE DEPTH	TOTAL WELL DEPTH	SCREENED INTERVAL	TOP OF SAND	TOP OF SEAL	WELL HEAD COMPLETION
Well S-1	28.0	25.5	5.5 - 25.5	4.0	2.0	Flush
Well S-2	39.7	39.7	19.7 - 39.7	17.7	13.7	Flush
Well S-3	39.5	39.5	19.5 - 39.5	17.5	15.5	Protective Casing
Well S-4	34.0	34.0	14.0 - 34.0	12.0	10.0	Protective Casing
Well S-5	30.0	28.0	8.0 - 28.0	5.3	2.5	Protective Casing
Well S-6	40.5	40.5	20.5 - 40.5	18.5	14.5	Flush
Well S-7	30.3	30.3	10.0 - 30.0	8.0	4.0	Flush
Well S-8	28.0	28.0	8.0 - 28.0	6.0	2.0	Flush
Well S-9	40.0	28.3	8.0 - 28.0	6.0	2.0	Flush
Well S-10	40.0	35.0	15.0 - 35.0	13.0	9.0	Flush
Well C-1	104.0	100.6	90.0 - 100.0	86.0	54.0	Flush
Well C-2	87.0	85.0	74.5 - 84.5	70.0	58.0	Flush
Well C-3	90.5	90.5	79.1 - 89.1	75.0	70.0	Protective Casing
Well C-4*	200.0	130.4	120.0 - 130.0	112.0	84.0	Protective Casing
Well C-5	92.5	91.0	80.5 - 90.5	76.0	63.0	Protective Casing

* Note: Well C-4 constructed with a double casing - outer (10") casing installed to 76' below ground surface - grouted at base of 10" casing, and from ground surface to a depth of 40' below ground surface.

All depths expressed in feet below ground surface

C₉

C₁₁

C₁₀

CLW

0000002186